

DVD/CD/MP3/FM/AM audio player



Features:

- Two independent audio outputs for DVD / USB / SD and FM / AM Tuner
- Two independent volumes can be set
- A combined audio output

Part-No.: X-MAP04

The X-MAP04 audio device features an integrated DVD/CD player, an MP3 player and an FM/AM tuner, as well as an USB/SD interface. The device supports two modes of operation. Mode of operation 1: DVD/USB/SD and FM/AM tuner can be operated simultaneously via two separate ports. Mode of operation 2: DVD/USB/SD and FM/AM tuner can be switched. The selected signal is transmitted via a joint port. DVD videos and JPEG are supported. The connection to the VARIODYN D1 system is done via a cinch audio link. Suitable for 24-hour operation.

DVD\CD\Audio

Output voltage	2 V DC
Signal-to-noise ratio	80 dB
Channel separation	75 dB

Tuner

Common technical data

Rated voltage	100 - 24 V AC
Power consumption	15 W
Outputs	1 x Cinch for FM/AM-Tuner, 1 x Cinch for DVD/USB/SD, 1 x Cinch for mixed signals
Weight	approx. 3.8 kg
Dimensions	W: 482 mm H: 44 mm D: 236 mm (1 HU)